



- NOTES**
1. ALL METAL POSTS AND WOOD OFFSET BLOCKS SHALL BE AS SHOWN ON STANDARD MD 605.23.
 2. THE W BEAM TERMINAL CONNECTORS AND W BEAM SECTIONS SHALL BE LAPPED IN THE DIRECTION OF TRAFFIC.
 3. THE MEDIAN TRAFFIC BARRIER W BEAM SHALL BE AS SHOWN ON STANDARD 605.28.
 4. THE COST FOR THE PRECAST TEMPORARY 32 INCH F SHAPE CONCRETE TRAFFIC BARRIER TERMINAL END WILL BE PAID FOR PER EACH.

SPECIFICATION 104	CATEGORY CODE ITEMS
APPROVED	<i>Kirk G. McCall</i> DIRECTOR - OFFICE OF HIGHWAY DEVELOPMENT
	APPROVAL • SHA REVISIONS
	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION
	APPROVAL 2-10-04
	APPROVAL 3-31-04
REVISION	REVISION
REVISION	REVISION
REVISION	REVISION

Maryland Department of Transportation
STATE HIGHWAY ADMINISTRATION
 STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES
TRAFFIC BARRIER W BEAM MEDIAN BARRIER
ANCHORAGE AT PRECAST 32 INCH F SHAPE TEMPORARY
CONCRETE TRAFFIC BARRIER TERMINAL END
STANDARD NO. MD 104.01-62