


NOTES

1. LONGITUDINAL UNDERDRAIN SHALL BE PLACED ACCORDING TO THE PLANS OR AS DIRECTED BY THE ENGINEER.
2. THE UNDERDRAIN TRENCH SHALL NOT BE CONSTRUCTED BEFORE PLACEMENT OF THE MAINLINE PAVING.
3. GEOTEXTILE CLASS SHALL BE AS SPECIFIED IN THE PLANS OR SPECIAL PROVISIONS.
4. AGGREGATE SHALL CONFORM TO SECTION 901 OF THE STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS.
5. AGGREGATE SHALL BE TAMPED WITH A LIGHT VIBRATORY TAMPER PRIOR TO OVERLAPPING THE GEOTEXTILE FABRIC.
6. CONTRACT UNIT PRICE BID PER LINEAR FOOT FOR 6" PERFORATED CIRCULAR PIPE LONGITUDINAL UNDERDRAIN SHALL CONSTITUTE FULL COMPENSATION FOR ALL MATERIALS, LABOR, EQUIPEMENT AND INCIDENTALS NECESSARY TO DO THE WORK.



GEOTEXTILE FABRIC
DETAIL

SPECIFICATION 306	CATEGORY CODE ITEMS										
APPROVED	<i>Kirk G. McCall</i> DIRECTOR - OFFICE OF HIGHWAY DEVELOPMENT										
SHA State Highway Administration	<table> <tr> <td>APPROVAL • SHA REVISIONS</td><td>APPROVAL • FEDERAL HIGHWAY ADMINISTRATION</td></tr> <tr> <td>APPROVAL 3-6-86</td><td>APPROVAL 4-14-86</td></tr> <tr> <td>REVISED 10-1-01</td><td>REVISED 3-21-88</td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> </table>	APPROVAL • SHA REVISIONS	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION	APPROVAL 3-6-86	APPROVAL 4-14-86	REVISED 10-1-01	REVISED 3-21-88	REVISED	REVISED	REVISED	REVISED
APPROVAL • SHA REVISIONS	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION										
APPROVAL 3-6-86	APPROVAL 4-14-86										
REVISED 10-1-01	REVISED 3-21-88										
REVISED	REVISED										
REVISED	REVISED										

Maryland Department of Transportation
STATE HIGHWAY ADMINISTRATION
STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES
**LONGITUDINAL UNDERDRAIN LOCATED AT
PAVEMENT EDGE FOR RIGID PAVEMENT**

STANDARD NO. MD 387.12