


## NOTES

1. LONGITUDINAL UNDERDRAIN SHALL BE PLACED ACCORDING TO THE PLANS OR DIRECTED BY THE ENGINEER.
2. THE UNDERDRAIN TRENCH SHALL NOT BE CONSTRUCTED BEFORE PLACEMENT OF THE BASE (SUBBASE) COURSE.
3. GEOTEXTILE CLASS SHALL BE AS SPECIFIED IN THE PLANS OR SPECIAL PROVISIONS.
4. AGGREGATE SHALL CONFORM TO SECTION 901 OF STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS.
5. AGGREGATE SHALL BE TAMPED WITH A LIGHT VIBRATORY TAMPER PRIOR TO OVERLAPPING THE GEOTEXTILE FABRIC.
6. CONTRACT UNIT PRICE BID PER LINEAR FOOT FOR 6" PERFORATED CIRCULAR PIPE LONGITUDINAL UNDERDRAIN SHALL CONSTITUTE FULL COMPENSATION FOR ALL MATERIALS, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO DO THE WORK.



**GEOTEXTILE FABRIC**  
DETAIL

SPECIFICATION <b>306</b>	CATEGORY CODE ITEMS										
APPROVED	<i>Kirk G. McCall</i> DIRECTOR - OFFICE OF HIGHWAY DEVELOPMENT										
<b>SHA</b> State Highway Administration	<table> <tr> <td>APPROVAL • SHA REVISIONS</td><td>APPROVAL • FEDERAL HIGHWAY ADMINISTRATION</td></tr> <tr> <td>APPROVAL <b>3-6-86</b></td><td>APPROVAL <b>4-14-86</b></td></tr> <tr> <td>REVISED <b>10-1-01</b></td><td>REVISED <b>3-21-88</b></td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> <tr> <td>REVISED</td><td>REVISED</td></tr> </table>	APPROVAL • SHA REVISIONS	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION	APPROVAL <b>3-6-86</b>	APPROVAL <b>4-14-86</b>	REVISED <b>10-1-01</b>	REVISED <b>3-21-88</b>	REVISED	REVISED	REVISED	REVISED
APPROVAL • SHA REVISIONS	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION										
APPROVAL <b>3-6-86</b>	APPROVAL <b>4-14-86</b>										
REVISED <b>10-1-01</b>	REVISED <b>3-21-88</b>										
REVISED	REVISED										
REVISED	REVISED										

**Maryland Department of Transportation**  
**STATE HIGHWAY ADMINISTRATION**  
STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES

**LONGITUDINAL UNDERDRAIN LOCATED AT  
SHOULDER EDGE FOR RIGID PAVEMENT**

**STANDARD NO. MD 387.21**