I. GENERAL

This project involves the modification of existing Traffic Control Signals (pedestrian signals and pushbuttons) at the intersections of: MD 45 and Pennsylvania Avenue, MD 45 and Chesapeak Avenue & MD 45 and Towsontown Boulevard in Baltimore County. MD 45 (York Road) is assumed to run a north-south

#### II. INTERSECTION OPERATION

The phasing operation at each of the three intersections shall not be changed. The existing semi-actuated eight-phase controller and NEMA cabinet shall be utilized at each of the three locations.

## MD 45 and Pennsylvania Avenue

1. The existing pedestrian signals across the north and south legs of MD 45 shall be replaced with 16" LED countdown pedestrian signals. The existing pedestrian signals across the east and west legs of Pennsylvania Avenue shall remain the same.

#### MD 45 and Chesapeake Avenue

1. The existing pedestrian signals across the north and south legs of MD 45 shall be replaced with 16" LED countdown pedestrian signals. The existing pedestrian signals across the east and west legs of Chesapeake Avenue shall remain the same.

### [7] MD 45 and Towsontown Boulevard

1. The existing pedestrian signals and pushbuttons across the north,⊅Act south †legs of MD 45 shall be replaced with 16" LED countdown pedestrian signals and new pushbuttons. The existing pedestrian signals across the east and west legs of Towsontown Boulevard shall remain the same.

### III. SPECIAL NOTES

- 1. The Contractor shall be responsible for terminating all signal cables. excluding interconnect, to the appropriate terminals and shall properly label each cable.
- 2. All controller cabinet wiring will be performed by the S.H.A. Signal Shop Contact Mr. Ed Rodenhizer at (410) 787-7650 seventy-two hours in advance of intended work.
- 3. All underground and overhead utilities shown on these plans are schematic only and may not be complete. The Contractor shall be responsible for notifying Miss Utility prior to construction so that all utilities may be located in the field. If the Contractor perceives that a conflict between the utilities and the traffic signal will occur, the Contractor shall notify the Project Engineer immediately so that the conflict may be resolved.

### EQUIPMENT LIST

A. EQUIPMENT TO BE SUPPLIED BY S.H.A..

THERE IS NO EQUIPMENT TO BE SUPPLIED BY THE SHA.

EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR

	ITEM				
	NO.	DESCRIPTION	QUAN	YTITY	
	1001	Maintenance of traffic per assignment.	1	EA	
	5003	Furnish and install 12" heat applied white permanent preformed thermoplastic pavement markings.	1860	LF	
	5004	Furnish and install 24" heat applied white permanent preformed thermoplastic 1 pavement markings.	210	LF	
	5005	Removal of existing permanenet pavement line markings — any width.	2070	LF	
1	8000	Furnish and install 16" 1 Way LED Countdown Ped. Signal	<b>≯</b> & 14	EA []	
	8011	Furnish and install pushbutton and sign.	4	EA	
	8013	Remove and dispose of existing material and equipment per assignment.	1	EA	

C. EQUIPMENT TO BE REMOVED

BRUDIS & ASSOCIATES, INC.

9220 RUMSEY ROAD SUITE 110 COLUMBIA: MARYLAND 21045

410-884-3607 410-884-3609(FAX)

All removed signal materials are to become property of the Contractor.

Relocate ground mounted sign. 17 SF

MD 45 (YORK ROAD) AND PENNSYLVANIA AVENUE

PHASE CHART

THERE IS NO CHANGE TO THE PHASING CHART

MD 45 (YORK ROAD) AND CHESAPEAKE AVENUE

PHASE CHART

THERE IS NO CHANGE TO THE PHASING CHART

MD 45 (YORK ROAD) AND TOWSONTOWN BOULEVARD

PHASE CHART

THERE IS NO CHANGE TO THE PHASING CHART

MD 45 (YORK ROAD) AND PENNSYLVANIA AVENUE

WIRING DIAGRAM

THERE IS NO CHANGE TO THE WIRING DIAGRAM

MD 45 (YORK ROAD) AND CHESAPEAKE AVENUE

WIRING DIAGRAM

THERE IS NO CHANGE TO THE WIRING DIAGRAM

MD 45 (YORK ROAD) AND TOWSONTOWN BOULEVARD

WIRING DIAGRAM

THERE IS NO CHANGE TO THE WIRING DIAGRAM

The contact persons for District #4 are as follows:

Randall Scott, Assistant District Engineer - Traffic, 410-321-2781 Daniel Witt, Assistant District Engineer - Construction, 410-321-2821 Steve Marciszewski, Assistant District Engineer - Maintenanace, 410-321-2761 Suenette Pope, Utility Engineer, 410-321-2841 Richard L. Daff, Sr., Chief Traffic Operations Division, 410-787-7630 Edward D. Rodenhizer, Chief Signal Operations, 410-787-7652

# 1 REDLINE REVISION - MARCH 31, 2005

INSTALL COUNTDOWN PEDESTRIAN SUGNAL INDICATIONS FOR THE WASTELEG OF THE MD 45 (YORK ROAD) AND TOWSONTOWN BOULEVARD INTERSECTION.

DRAWING NO.

STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION OFFICE OF TRAFFIC & SAFETY TRAFFIC ENGINEERING DESIGN DIVISION

MD 45 (YORK ROAD) -PEENSYLVANIA AVE, CHESAPÉAKE AVE & TOWSONTOWN BLVD GENERAL INFORMATION SHEET

SCALE 1' = 20' DATE 3/3/05 CONTRACT NO. AT6045185 COUNTY BALTIMORE DESIGNED BY \_\_\_\_\_CJP DRAWN BY CJP LOGMILE 01.86 TO 02.78 CHECKED BY RJM T.I.M.S. NO.\_\_\_\_ TOS NO.\_\_ F.A.P. NO.\_

SHEET NO. 4 OF 4

·· OF

PLOTTED: \$DATETIME\$
FILE: \$FILE\$

SURVEY BOOK NO.

STRUCTURE INVENTORY NO.