

GENERAL NOTES

- I. FOR 5 INCH CONCRETE SIDEWALK RECONSTRUCTION, SEE TYPICAL SECTION, SHEET DE-I.
- 2. ALL DIMENSIONS ARE APPROXIMATE. CONTRACTOR TO VERIFY ALL DIMENSIONS IN THE FIELD.
- 3. NO DISTURBED AREA SHALL BE LEFT UNSTABILIZED OVERNIGHT UNLESS THE RUNOFF IS DIRECTED TO AN APPROVED SEDIMENT CONTROL DEVICE.
- 4. SIDEWALK RECONSTRUCTION LIMITS SHALL COINCIDE WITH CRACK CONTROL JOINTS (JOINTER GROOVES) OR EXPANSION JOINTS IN EXISTING SIDEWALK. NEW EXPANSION JOINTS SHALL BE PROVIDED AT THE INTERFACE OF EXISTING AND PROPOSED SIDEWALK. SEE SHA. STD. NO. MD-655.01.
- 6. INSTALL DETECTABLE WARNING SURFACE (TYPE 3 BRICK PAVERS)
 ON SIDEWALK RAMP AS PER SHA STD. NO. MD-655.40.
- 7. FORM NEW SIDEWALK AND EXPANSION JOINT MATERIAL AROUND EX.UTILITY POLES, MANHOLE COVERS, VALVE COVERS, AND FIRE HYDRANTS AS NECESSARY.
- 8. RESET ANY SIGNS DISTURBED BY THE CONSTRUCTION AS DIRECTED BY THE ENGINEER.
- 9. EXISTING INLETS SHALL NOT BE DAMAGED DURING CONSTRUCTION.

 DAMAGE TO THE INLETS WILL REQUIRE THE INLET TO BE REPLACED AT NO ADDITIONAL COST TO THE ADMINISTRATION.
- IO. EXISTING TREES, SHRUBS, AND THEIR RESPECTIVE ROOT SYSTEMS SHALL NOT BE DISTURBED DURING CONSTRUCTION.

STANDARD TYPE 12 INCH GUTTER PAN	A COMBINATION CURB AND GUTTER 8 INCH DEPTH SHA STD. NO. MD-620.02
LOCATION	QUANTITY (LF)
SOUTHEAST QUADRANT	21
SOUTHEAST ISLAND	27
MEDIAN ISLAND 8	

STANDARD TYPE A CURB ANY DEPTH
LOCATION QUANTITY (LF)
SOUTHEAST ISLAND 15

5 INCH CONCRET	E SIDEWALK
LOCATION	QUANTITY (SF)
SOUTHEAST QUADRANT	178
SOUTHEAST ISLAND	210
MEDIAN ISLAND	3

CLASS 2 EXC	CAVATION
LOCATION	QUANTITY (CY
SOUTHEAST QUADRANT	1
SOUTHEAST ISLAND	0.5

HOT MIX ASPHALI	SUPERPAVE 9.5 MM FOR SURFACE, PG 76-22, LEVEL-3
LOCATION	QUANTITY (TON)
SOUTHEAST QUADRANT	0.5
SOUTHEAST ISLAND	0,5
MEDIAN ISLAND	0,5

_		
	MIX NO.9 FOR SL	OT BACKFILL
[LOCATION	QUANTITY (LF)
ſ	SOUTHEAST QUADRANT	21
[SOUTHEAST ISLAND	27
[MEDIAN ISLAND	10

DETECTABLE WA (TYPE 3 BRI SHA STD.NO	CK PAVERS)
LOCATION	QUANTITY (SF)
SOUTHEAST QUADRANT	11
SOUTHEAST ISLAND	21

PLACING FURNISHED TOPSOIL 4-INCH DEPTH

LOCATION QUANTITY (SY)

SOUTHEAST QUADRANT II

SOUTHEAST ISLAND 5

TURFGRASS SOD	ESTABLISHMENT
LOCATION	QUANTITY (SY)
SOUTHEAST QUADRANT	

SOUTHEAST ISLAND



STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION

MD 166 (ROLLING ROAD) AT BLOOMSBURY AVENUE

REVISIONS	RAMP DETAILS		
	SCALE1" = 5' DATE SEPTE	EMBER 2012 CONTRACT NO. XX15	15133
	DESIGNED BY JDG	COUNTY BALTIMORE	
	DRAWN BY JBB	LOGMILE 03016601.74	
	CHECKED BY ATD	TIMS NO. L650	
	FAP NO	TOD NO.	
	TS NO. 3207G-DE DRAWING DE-2	OF 2 SHEET NO. 6 OF	- 6
PLOTTED: SDATES	<u> </u>		

PLOTTED: \$DATE\$ FILE: \$FILE\$