

PROJECT DESCRIPTION

GENERAL

THIS PROJECT INVOLVES THE FULL RECONSTRUCTION OF THE TRAFFIC SIGNAL AT THE INTERSECTION OF MD 97 (GEORGIA AVENUE) AND AUGUST DRIVE. ACCESSIBLE PEDESTRIAN PUSHBUTTONS AND COUNTDOWN PEDESTRIAN SIGNALS WILL BE INSTALLED FOR THE NORTH LEG CROSSING. VIDEO DETECTION IS PROPOSED FOR SB LEFT TURN AND SIDE STREET PRESENCE DETECTION.

MD 97 IS ASSUMED TO RUN IN A NORTH-SOUTH DIRECTION.

INTERSECTION OPERATION

THE INTERSECTION WILL CONTINUE TO OPERATE IN A FOUR PHASE, FULL-TRAFFIC-ACTUATED MODE. THE EXISTING SIDE STREET PEDESTRIAN PHASE AND THE EXISTING SOUTHBOUND EXCLUSIVE/PERMISSIVE LEFT-TURN PHASE WILL REMAIN.

CONTROLLER REQUIREMENTS

INSTALL A NEW EIGHT-PHASE FULLY ACTUATED TRAFFIC SIGNAL CONTROLLER AND ASSOCIATED HARNESSSES IN A NEMA SIZE "6" BASE MOUNTED CABINET. THE MONTGOMERY COUNTY SIGNAL SHOP WILL INSTALL ONE (1) VIDEO DETECTION INTERFACE FOR 1-4 CAMERAS AND ONE (1) CENTRAL CONTROL UNIT.

APS WILL FUNCTION AS FOLLOWS:

FOR MD 97 (GEORGIA AVENUE)

- A. WHEN A PEDESTRIAN LOCATES AND PRESSES THE PUSHBUTTON FOR AN EXTENDED TIME, THE PUSHBUTTON MESSAGE WILL BE "WAIT TO CROSS GEORGIA AT AUGUST, WAIT."
- B. WHEN THE "WALK" PHASE BEGINS, THE MESSAGE WILL BE A RAPID TICK, WHICH WILL LAST FOR THE DURATION OF THE "WALK" PHASE.

THE CONTACT PERSONS FOR DISTRICT #3 ARE AS FOLLOWS:

Mr. Cedric Ward
Assistant District Engineer - Traffic
Phone: 301-513-7356

Mr. Victor Grafton
District Utility Engineer
Phone: 301-513-7350

Mr. Vernon Stinnett
Assistant District Engineer - Maintenance
Phone: 301-513-7304

OFFICE OF TRAFFIC AND SAFETY:

Mr. Richard L. Daff Sr.
Chief, Traffic Operations Division
Phone: 410-787-7630

Mr. Robert Snyder
Assistant Division Chief, Traffic Operations
410-787-7630

Mr. Edward Rodenhizer
Team Leader, Signal Operations
Phone: 410-787-7650

Mr. Eugene Bailey
Team Leader, Sign Operations
410-787-7670

Montgomery County

Mr. Kamal Hamud
Traffic Engineering
240-777-8761

Mr. Bob Ricketts
Signal Shop
301-279-1975

The Power Company is:
Pepco
8300 Old Marlboro Pike
Upper Marlboro, MD 20442
Phone: 301-961-5325

EQUIPMENT LIST 'A'

EQUIPMENT TO BE FURNISHED BY THE SHA.

ITEM NO.	QUANTITY	DESCRIPTION
9044	1 EA	[UPDATED] CONTROLLER CABINET, SIZE 6
9086	1 EA	[UPDATED] VIDEO DETECTION INTERFACE EQUIPMENT: 1-4 CAMERAS
9570	41 SF	[UPDATED] SHEET ALUMINUM GROUND MOUNTED SIGN: 1 EA - M1-5(6) (24 IN. X 48 IN.) "NORTH, MD 97, RIGHT ARROW" 3 EA - S1-1 (36 IN. X 36 IN.) F.Y.G. 3 EA - W16-7p(L) (24 IN. X 12 IN.) F.Y.G.
9571	52 SF	[UPDATED] SHEET ALUMINUM MAST ARM / POLE MOUNTED SIGN: 1 EA - D-3(1) (96 IN. X 16 IN.) "GEORGIA AVE" 2 EA - D-3(1) (96 IN. X 16 IN.) DUAL FACED "AUGUST DR" 2 EA - R10-3(1) (9 IN. X 15 IN.) "PUSH BUTTON TO CROSS GEORGIA AVENUE" 1 EA - M1-5(6) (36 IN. X 72 IN.) "SOUTH, MD 97, LEFT ARROW"

EQUIPMENT LIST 'A-I'

EQUIPMENT TO BE FURNISHED BY MONTGOMERY COUNTY

ITEM NO.	QUANTITY	DESCRIPTION
9000	1 EA	INTERCONNECT SPLICE CABINET

EQUIPMENT LIST 'C'

EQUIPMENT TO BE REMOVED AND RETURNED TO SHA.

ITEM NO.	QUANTITY	DESCRIPTION
----------	----------	-------------

NONE - ALL EQUIPMENT TO BE REMOVED SHALL BECOME PROPERTY OF THE CONTRACTOR.


EQUIPMENT LIST 'B'

EQUIPMENT TO BE FURNISHED AND INSTALLED BY THE CONTRACTOR.


ITEM NO.	QUANTITY	DESCRIPTION
1001	3 EA	MAINTENANCE OF TRAFFIC
2002	6 CY	TEST PIT EXCAVATION
5003	225 LF	REMOVAL OF EXISTING PERMANENT PREFORMED PAVEMENT LINE MARKINGS ANY WIDTH
5005	160 LF	12 INCH WHITE PREFORMED THERMOPLASTIC PAVEMENT MARKING LINES
5006	15 LF	24 INCH WHITE PREFORMED THERMOPLASTIC PAVEMENT MARKING LINES
6002	100 LF	STANDARD TYPE A COMBINATION CURB AND GUTTER 12 IN. GUTTER PAN 8 IN. DEPTH
6004	675 SF	5 INCH CONCRETE SIDEWALK
8000	1 EA	INSTALL INTERCONNECT SPLICE CABINET
8001	25 EA	12 INCH LED SIGNAL HEAD SECTION
8002	1 EA	2 WIRE CENTRAL CONTROL UNIT
8007	2 EA	AUDIBLE/TACTILE PEDESTRIAN PUSHBUTTON STATION & SIGNS
8011	1 EA	EMBEDDED METERED SERVICE PEDESTAL
8020	2 EA	LED 16 INCH COUNTDOWN PEDESTRIAN SIGNAL HEADS
8022	1 EA	MAST ARM POLE & 38 FT. MAST ARM ANY "T" DIMENSION
8023	1 EA	MAST ARM POLE & 50 FT. MAST ARM ANY "T" DIMENSION
8025	1 EA	MAST ARM POLE & 60 FT. MAST ARM ANY "T" DIMENSION
8028	2 EA	PED POLE (ANY SIZE)
8029	1 EA	REMOVE & DISPOSE MATERIAL & EQUIPMENT PER ASSIGNMENT
8034	2 EA	VIDEO DETECTION CAMERA & CABLE
8035	80 LF	12 PAIR COMMUNICATION CABLE, SELF-SUPPORTING AND/OR JELLYFILLED
8036	30 LF	3 INCH ELECTRICAL CONDUIT-PVC RISER
8038	50 LF	CABLE-1 CONDUCTOR, 250 KCML, CU, USE, 600V
8039	125 LF	DISCONNECT, PULL-BACK AND REROUTE CABLES
8041	165 LF	SCHEDULE 80 RIGID PVC CONDUIT UP TO 4 INCHES - BORED
8042	105 LF	SCHEDULE 80 RIGID PVC CONDUIT UP TO 4 INCHES - SLOTTED
8043	125 LF	SCHEDULE 80 RIGID PVC CONDUIT UP TO 4 INCHES - TRENCHED
8044	70 LF	WOOD SIGN SUPPORTS UP TO 4 X 6 INCHES
8045	40 SF	DETECTABLE WARNING SURFACES
8046	93 SF	INSTALL GROUND MOUNTED AND/OR OVERHEAD SIGN
8048	385 LF	NO. 6 AWG STRANDED BARE COPPER GROUND WIRE
8050	1 EA	WEATHER HEAD, 3 INCH
8053	60 LF	ELECTRICAL CABLE 1-CONDUCTOR NO. 4 AWG-THHN/THWN
8054	5 EA	FURNISH AND INSTALL ELECTRICAL HANDHOLE
8062	280 LF	ELECTRICAL CABLE - 2 CONDUCTOR (NO. 14 AWG)
8064	370 LF	ELECTRICAL CABLE - 5 CONDUCTOR (NO. 14 AWG)
8065	735 LF	ELECTRICAL CABLE - 7 CONDUCTOR (NO. 14 AWG)
8073	1 EA	INSTALL CONTROLLER AND CABINET - BASE MOUNT

SIGNAL POLE AND PAVEMENT MARKING DETAIL

(SCALE 1"=20')



WIRING DIAGRAM



RE-ROUTE EX. INTERCONNECT CABLE - NORTH FROM DENNIS AVENUE

RE-ROUTE EX. INTERCONNECT CABLE - SOUTH FROM FOREST GLEN RD.

12 PAIR COMMUNICATION CABLE - JELLYFIELD

NO. 6 AWG STRANDED BARE COPPER GROUND WIRE

ELECTRICAL CABLE 1- CONDUCTOR NO. 4 AWG-THHN/THWN

PROPOSED UNDERGROUND POWER SERVICE CABLE 1-CONDUCTOR, 250 KCML, CU, USE, 600V

PROPOSED GROUND ROD - 3/4 IN. DIAMETER X 10 FOOT LENGTH

PULL BACK EX. INTERCONNECT CABLE - NORTH FROM DENNIS AVENUE

PULL BACK EX. INTERCONNECT CABLE - SOUTH FROM FOREST GLEN RD.

PULL BACK EX. INTERCONNECT CABLE - SOUTH FROM FOREST GLEN RD.

STV
STV Incorporated
7125 Ambassador Road, Suite 200
Baltimore, MD 21244
www.stvinc.com



STATE OF MARYLAND
DEPARTMENT OF TRANSPORTATION
STATE HIGHWAY ADMINISTRATION
OFFICE OF TRAFFIC & SAFETY
TRAFFIC ENGINEERING DESIGN DIVISION
MD 97 (GEORGIA AVENUE) AT AUGUST DRIVE

WHEATON, MARYLAND

GENERAL INFORMATION

SCALE NONE ADVERTISED DATE 2-1-2011 CONTRACT NO. XX6315185

DESIGNED BY MCG COUNTY MONTGOMERY

DRAWN BY MCG LOGMILE 15009702.02

CHECKED BY MTS TMS NO. K534

F.A.P. NO. TOD NO.

TS NO. 3290C-GI DRAWING SG-02 OF 02 SHEET NO. 02 OF 02

PLOTTED: Wednesday, February 09, 2011 AT 05:59 PM
FILE: I:\PROJECTS\4014255\4014255_0037\Drawings\TRA\PSG-N000_m097.dgn