MD 182 RUNS IN A NORTH-SOUTH DIRECTION.

REGION NO

EQUIPMENT LISTS

A. EQUIPMENT	TO BE FURNISHED	BY THE SHA
ITEM NO.	CUANTITY	DESCRIPTION
	92.6 S.F.	1 EACH ASSOCIATED SHIELD ASSEMBLY SIGN, "NORTH, MARYLAND 182, (RIGHT ARROW)", 30" x 51".
		POLE MOUNTED HARDWARE 1 EACH ASSOCIATED SHIELD ASSEMBLY SIGN, "SOUTH, MARYLAND 182, (LEFT ARROW)", 48" x 75",
		POLE MOUNTED HARDWARE 1 EACH ASSOCIATED SHIELD ASSEMBLY SIGN, "SOUTH, MARYLAND 182, (RIGHT ARROW)", 30" x 51",
		POLE MOUNTED HARDWARE 1 EACH ASSOCIATED SHIELD ASSEMBLY SIGN, "NORTH, MARYLAND 182, (LEFT ARROW)", 48" x 75",
		POLE MOUNTED HARDWARE 1 EACH D3-2 DUAL FACED SIGN, "(LEFT ARROW) Bel Pre Road", "Bonifant Road (RIGHT ARROW),
. '		32" x Var., MAST ARM MOUNTED HARDWARE

B. EQUIPMENT TO BE FURNISHED AND/ OR INSTALLED BY THE CONTRACTOR

	1001	QUANTITY 1 EACH	DESCRIPTION MAINTENANCE OF TRAFFIC
	2002	1 C.Y.	TEST PIT EXCAVATION
	5004	825 L.F.	 F & I 12" WHITE HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING
	5005	235 L.F.	F & I 24" WHITE HEAT APPLIED THERMOPLASTIC PAVEMENT MARKING
-	5008	1.060 L.F.	REMOVE EXISTING PAVEMENT MARKING TAPE - ANY WIDTH
	8011	42 EACH	 F & I 12" BLACK FACED VECHICULAR SIGNAL HEAD SECTION
	8019	12 EACH	F & I 8" BLACK FACED VECHICULAR SIGNAL HEAD SECTION
	8048	1 EACH	 REMOVE AND DISPOSE OF EXISTING MATERIAL PER ASSIGNMENT
	8076	71.3 S.F.	INSTALL GROUND MOUNTED SIGN
	8077	21.3 S.F.	INSTALL OVERHEAD SIGN

C. EQUIPMENT TO BE REMOVED AND RETURNED TO THE SHA

ALL REMOVED SIGNAL MATERIALS ARE TO BECOME THE PROPERTY OF THE CONTRACTOR

PHASE CHART

THERE IS NO CHANGE TO THE EXISTING PHASING

PROJECT CONTACTS

THE PROJECT CONTACTS ARE AS FOLLOWS:

MR. MAJID SHAKIB
ASSISTANT DISTRICT ENGINEER - TRAFFIC
PHONE: (301) 513-7358 MR. RICHARD DAFF CHIEF, TRAFFIC OPERATIONS DIVISION PHONE: (410) 787-7630


MR. RALEIGH MEDLEY
ASSISTANT DISTRICT ENGINEER - MAINTENANCE
PHONE: (301) 513-7304 MR. ROBERT SNYDER
ASSISTANT DIVISION CHIEF, TRAFFIC OPERATIONS DIVISION PHONE: (410) 787-7631


MR. AUGIE REBISH ASSISTANT DISTRICT ENGINEER - UTILITIES PHONE: (301) 513-7350

MR. EDWARD RODENHIZER CHIEF, SIGNAL OPERATIONS SECTION PHONE: (410) 787-7652

WIRING DIAGRAM

A-H = USE THE EXISTING 7-CONDUCTOR CABLE (NO. 14 AWG)
I-L = USE THE EXISTING 5-CONDUCTOR CABLE (NO. 14 AWG)





TRAFFIC ENGINEERING DESIGN DIVISION MD 182 (LAYHILL ROAD) and BEL PRE ROAD/ BONIFANT ROAD

LAYHILL, MARYLAND

F.A.P. NO.
S.H.A. NO. MO6 9 AS6 BS6 TS-2402 A
COUNTY MONTGOMERY. T.I.M.S. NO. DRAWN BY: W. Malcolm CHECKED BY: SCALE: NOT TO SCALE LOG MILE 15018202,23 DATE: 11/ 2001