## PROJECT DESCRIPTION GENERAL THIS PROJECT INVOLVES THE MODIFICATION OF A EXISTING TRAFFIC SIGNAL AT US 29 AND DETOUR ROAD IN MONTGOMERY COUNTY, US 29 IS ASSUMED TO RUN IN A NORTH-SOUTH DIRECTION. INTERSECTION OPERATION THE INTERSECTION WILL OPERATE IN A SIX PHASE FULL TRAFFIC-ACTUATED MODE WITH THE US 29 APPROACHES RUNNING CONCURRENTLY AND DETOUR ROAD APPROACHES OPERATING AS A SPLIT PHASE. EXCLUSIVE LEFT TURN PHASING WILL BE PROVIDED FOR THE US 29 APPROACHES. SPECIAL NOTES I. THE FOLLOWING CONTACT PEOPLE FOR THIS PROJECT ARE AS FOLLOWS:

MR. LEE STARKLOFF, ASSISTANT DISTRICT ENGINEER-TRAFFIC PHONE: (301) 513-7300
MR. DENNIS MCMAHAN, ASSISTANT DISTRICT ENGINEER-CONSTRUCTION MR. DENNIS McMAHAN, ASSISTANT DISTRICT ENGINEER-CONSTRUCTION PHONE: (310) 513-7336

MR. RALEIGH MEDLEY, ASSISTANT DISTRICT ENGINEER-MAINTENANCE PHONE: (301) 513-7300

MR. AUGIE REBISH, ASSISTANT DISTRICT ENGINEER-UTILITY PHONE: (301) 513-7300

MR. RICHARD L. DAFF, Sr., CHIEF TRAFFIC OPERATIONS DIVISION PHONE: (410) 787-7630

MR. BOBBY GONZALES, TRAFFIC ENGINEER MCDPWT PHONE: (240) 777-8761

MR. MIKE KINNEY MCDPWT (FOR SURVEILLANCE CAMERA)

MR. MIKE KINNEY, MCDPWT (FOR SURVEILLANCE CAMERA) PHONE: (240) 777-8760

2. MAINTENANCE OF TRAFFIC WILL BE HANDLED BY THE CONTRACTOR UTILIZING THE STANDARD PLATES FOR TRAFFIC CONTROL:

## EQUIPMENT LIST

A. EQUIPMENT TO BE SUPPLIED BY THE ADMINISTRATION. CATEGORY DESCRIPTION CODE NO.

UNITS QUANTITY

NONE

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR.

CATEGORY UNITS QUANTITY DESCRIPTION CODE NO. 340 24" HEAT APPL. WHT. PERM. PREF. THER. PVT. MARK. 585624

C. MATERIALS TO BE REMOVED BY THE CONTRACTOR. ALL MATERIALS TO BE REMOVED BY THE CONTRACTOR SHALL BECOME PROPERTY OF THE CONTRACTOR.

WIRING DIAGRAM

NO CHANGE

PHASE CHART

NO CHANGE

PHASE 3

SHEET NO.

MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic Q. Cafet. TRAFFIC ENGINEERING DESIGN DIVISION
GENERAL INFORMATION PLAN

DETOUR ROAD AT US 29



