



CONSTRUCTION DETAILS CONTINUED

- P. INSTALL NON-INVASIVE DETECTOR WITH 1000 FT. LEAD-IN CABLE.
- Q. INSTALL 200 AMP METERED SERVICE PEDESTAL.
- R. INSTALL 2 IN. PVC SCHEDULE 80 ELECTRICAL CONDUIT - TRENCHED.
- S. INSTALL 2 IN. PVC SCHEDULE 80 ELECTRICAL CONDUIT FOR TELEPHONE SERVICE - TRENCHED.
STUB UP CONDUIT BEND AT BASE OF UTILITY POLE.
- T. INSTALL 3 IN. PVC SCHEDULE 80 ELECTRICAL CONDUIT - BORED.



SABRA, WANG & ASSOCIATES, INC.
1504 JOH AVENUE
SUITE 160
BALTIMORE, MD 21227
(410) 737-6564
WWW.SABRA-WANG.COM

APPROVALS		REVISIONS		TRAFFIC SIGNAL PLAN	
<div style="position: relative; width: 100%; height: 100%;"> <div style="position: absolute; top: 0; left: 0; right: 0; bottom: 0; transform: rotate(-45deg); transform-origin: center; background: linear-gradient(to top right, transparent 49%, black 49%, black 51%, transparent 51%);"></div> <div style="position: absolute; top: 10px; left: 10px; transform: rotate(-45deg); font-weight: bold; font-size: 24px;">ORIGINAL ON FILE</div> </div>				SCALE <u>1"=20'</u> DATE <u>10/17/1975</u> CONTRACT NO. <u>C03215270</u>	
				DESIGNED BY <u>W. MILLER</u> COUNTY <u>CAROLINE</u>	
				DRAWN BY <u>A. BRUDMICHICK</u> LOGMILE <u>05001612.76</u>	
				CHECKED BY <u>T. I. M. S.</u>	
				F. A. P. NO. <u> </u> TOD NO. <u> </u>	
DIVISION CHIEF		© SIGNAL RECONSTRUCTION SWA CONTRACT NO. <u>C03215270</u> 04/05			
OFFICE DIRECTOR		SWA <u>10/21/1975</u> <u> </u> <u> </u>		DRAWING NO. <u>TS-1378C</u>	
				SHEET NO. <u> </u> OF <u> </u>	