

EQUIPMENT LIST "B"

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR

SPEC. SECTION	ITEM NO.	QUANTITY	DESCRIPTION
104	120500	L.S.	MAINTENANCE OF TRAFFIC
—	800000	L.S.	REMOVE AND DISPOSE OF EXISTING MATERIAL AND EQUIPMENT
—	873001	L.S.	REMOVE EXISTING SIGNAL EQUIPMENT TO BE SALVAGED
—	800000	L.S.	DELIVERY OF SALVAGED MATERIALS

EQUIPMENT LIST "C"

C. EQUIPMENT TO BE REMOVED BY THE CONTRACTOR AND DELIVERED TO THE STATE HIGHWAY ADMINISTRATION, 7941 CONNELLEY DRIVE, HANOVER, MARYLAND 21076.

QUANTITY	DESCRIPTION
4	30' STEEL POLE
1	TRAFFIC SIGNAL CONTROLLER AND CABINET
1	LIGHT STANDARD

- NOTES:
1. THE CONTRACTOR SHALL NOTIFY THE SHA AT 410-787-7652 AT LEAST THREE DAYS IN ADVANCE OF DELIVERY.
  2. ALL EQUIPMENT TO BE REMOVED AND NOT LISTED ABOVE SHALL BECOME THE PROPERTY OF THE CONTRACTOR.

CONSTRUCTION DETAILS

- A. REMOVE SPAN WIRE, SIGNS AND SIGNAL HEADS.
- B. REMOVE HANDHOLE.
- C. REMOVE BASE-MOUNTED CONTROLLER AND CABINET.
- D. REMOVE EXISTING STEEL POLES.
- E. REMOVE EXISTING LIGHT STANDARD.

PROJECT CONTACTS

THE CONTACT PERSONS FOR DISTRICT #3 ARE AS FOLLOWS:

MR. CHARLIE WATKINS  
DISTRICT ENGINEER  
PHONE: (301) 513-7311

MR. MAJID SHAKIB  
ASSISTANT DISTRICT ENGINEER - TRAFFIC  
PHONE: (301) 513-7358

MR. JOE GECKLE  
UTILITY ENGINEER  
PHONE: (301) 513-7350

MR. RICHARD L. DAFF, SR.  
CHIEF, TRAFFIC OPERATIONS DIVISION  
PHONE: (410) 787-7630

THE POWER COMPANY REPRESENTATIVE IS:  
BALTIMORE GAS AND ELECTRIC COMPANY  
MR. JOSEPH G. BUNCH  
SUPERVISOR  
INDUSTRIAL/COMMERCIAL SERVICES  
NEW BUSINESS CONSTRUCTION  
PHONE: (410) 859-9030

PROJECT DESCRIPTION

THIS PROJECT INVOLVES THE REMOVAL OF THE TRAFFIC SIGNAL AT MD 197 WESTBOUND AND MALLARD DRIVE IN PRINCE GEORGE'S COUNTY. MD 197 IS ASSUMED TO RUN IN A NORTH SOUTH DIRECTION.

THE EXISTING TRAFFIC SIGNAL SHALL BE REMOVED AT THE END OF STAGE 2 OF THE MAINTENANCE OF TRAFFIC. AT THIS TIME MD 197 AT THIS INTERSECTION BECOMES RIGHT IN AND RIGHT OUT.


MAINTENANCE OF TRAFFIC

THE TRAFFIC CONTROL NUMBERS SHALL BE REFERENCED FOR THE PROJECT

STANDARD NO. MD-105.00  
STANDARD NO. MD-105.01  
STANDARD NO. MD-105.02  
STANDARD NO. MD-105.101 (FLAGGING OPERATION)  
STANDARD NO. MD-105.103 (INTERSECTION FLAGGING OPERATION)  
STANDARD NO. MD-105.105 (SHOULDER WORK)  
STANDARD NO. MD-105.107 (LANE SHIFT)  
STANDARD NO. MD-105.109 (LANE SHIFT)  
NOTE: STANDARDS TO BE MODIFIED BY REPLACING W21-5 SIGN WITH A W29-1 SIGN (ROAD WORK AHEAD).

ADDENDUM

EXISTING TRAFFIC SIGNAL SS-28

 <b>RUMMEL, KLEPPER &amp; KAHL, LLP</b> CONSULTING ENGINEERS  81 MOSHER STREET BALTIMORE, MARYLAND 21217  TEL: (410) 728-2900 FAX: (410) 383-3270	REVISIONS:	APPROVALS:	MDOT - STATE HIGHWAY ADMINISTRATION <i>Office of Traffic &amp; Safety</i> TRAFFIC ENGINEERING DESIGN DIVISION LOG MILE # <u>16019712.02</u>	
			DRAWN BY: <u>SMH</u>	
			DES. BY: <u>SMH/DLA</u>	
			CHK. BY: <u>BJH</u>	
			MD 197 AT MALLARD DRIVE SIGNAL PLAN	
			COUNTY: <u>PRINCE GEORGE'S</u>	
			DATE: <u>FEBRUARY, 1999</u>	F.A.P. NO. <u>SEE TITLE SHEET</u>
			SCALE: <u>1"=20'</u>	S.H.A. NO. <u>N/A</u>
				TS/STD. NO.: <u>903H-G11</u>
				SHEET NO. <u>127A OF 367</u>

February, 1999  
Reconstruct Due To New  
Geometrics. SHA No: N/A  
DIRECTOR OFFICE OF TRAFFIC & SAFETY