PROJECT DESCRIPTION

I. GENERAL

This project involves the modification of an existing traffic control signal at the intersection of MD 410 (East-West Highway) and Toledo Terrace/Entrance to Home Depot in Hyattsville, Prince George's County. The modification includes modifying the eastbound and westbound MD 410 left turn phase from Exclusive/Permissive to Exclusive. The modification also includes replacing the interconnect cable from the signal cabinet at Toledo Terrace to the signal cabinet at Editor's Park Drive. MD 410 is assumed to run in an East—West direction.

II. INTERSECTION OPERATION

1. The intersection operates in a NEMA six-phase full-actuated mode, with MD 410 (East-West Highway) approaches running concurrently. Exclusive left—turn phases shall be provided for the eastbound and westbound approaches of MD 410 (East-West Highway). The side street shall continue to run concurrently.

III. APS FUNCTION AS FOLLOWS:

TO CROSS EAST-WEST HIGHWAY

- A. When a pedestrian locates and presses the pushbutton for an extended time, the pushbutton message is "Wait to cross East—West Highway at Toledo Terrace and Home Depot".
- B When the "WALK" phase begins, the message is a rapid tick, which will last for the duration of the "WALK" phase.

TO CROSS TOLEDO TERRACE

- A When a pedestrian locates and presses the pushbutton for an extended time, the pushbutton message is "Wait to cross Toledo Terrace at East—West Highway".
- B When the "WALK" phase begins, the message is a rapid tick, which will last for the duration of the "WALK" phase.

EQUIPMENT LIST

A. EQUIPMENT TO BE SUPPLIED BY THE S.H.A.

ITEM NO.	DESCRIPTION	QUANTITY	<u>UNIT</u>
MONE			

B. EQUIPMENT TO BE SUPPLIED AND /OR INSTALLED BY THE CONTRACTOR

ITEM NO.	DESCRIPTION	QUANTITY	<u>UNIT</u>
1001	MAINTENANCE OF TRAFFIC	1	EA
8001	12 INCH LED SIGNAL HEAD SECTION	18	EA
8023	NON-INVASIVE DETECTOR (ANY LENGTH) WITH LEAD-IN CABLE UP TO 1000 FEET	3	EA
8024	REMOVE & DISPOSE OF MATERIAL AND EQUIPMENT (PER ASSIGNMENT)	1	EA
8032	12-PAR COMMUNICATION CABLE, SELF-SUPPORTING, JELLY-FILLED / UNDERGROUND	850	LF
8038	UP TO 4 INCH SCHEDULE 80 RIGID PVC CONDUIT - BORED	70	LF
8039	UP TO 4 INCH SCHEDULE 80 RIGID PVC CONDUIT - SLOTTED	80	LF
8058	ELECTRICAL CABLE 7-CONDUCTOR (NO. 14 AWG)	500	LF

C. EQUIPMENT TO BE RETURNED TO THE S.H.A.

(ALL EQUIPMENT REMOVED SHALL BECOME THE PROPOERTY OF THE CONTRATOR)

CONTACT LIST

DICTRICT 3

OFFICE OF TRAFFIC & SAFETY

MR. VENU NEMANI ASSISTANT DISTRICT ENGINEER - TRAFFIC (PG) PHONE: (30I) 5I3-749I

MR. TOM FOUNTAIN ASSISTANT DISTRICT ENGINEER- MAINTENANCE PHONE: (30I) 5I3-7304

MR. VICTOR GRAFTON DISTRICT UTILITY ENGINEER PHONE: (301) 513-7350

MS. CORREN JOHNSON

CHIEF - TRAFFIC OPERATIONS DIVISION

PHONE: (410) 787- 7630 MR. ROBERT SNYDER ASSISTANT CHIEF - TRAFFIC OPERATIONS DIVISION

MR. EDWARD RODENHIZER MANAGER - SIGNAL OPERATIONS PHONE: (410) 787-7650


PHONE: (410) 787-7631

PHASE CHART

	1	2	3	4	5	6	/	8	9	10	11	12	13	14	15	16	1/	18	
			R Y G	R Y G			R Y G	R Y G	R Y G	RYG	R Y G	(R) Y) G	R Y G	R Y G					
PHASE 1+5	4 −G−	← G−	R	R	4 -G_	← G−	R	R	R	R	R	R _	R	R	DW	DŴ	DW	DW	
CHANGES TO	O PHASE	1+6, F	PHASE	2+5, OF	R PHAS	E 2+6												!	Ų.
PHASE 1+6	← G−	4 −G−	G	G	4 −R−	← R-	R	R	R	, R	. R	R	R	R	DW	DW,	DM	DW	Ŷ
1 CHANGE	← Y−	← Y−	G	G	4 −R−	← R-	R	R	R	R	R	R	R	R	DW	DW,	DW	DW	
PHASE 2+5	∢ R	4 −R−	R	R	4 -G−	← G−	G	G	R	R	R	R	R	R	DW	DW	ĎŴ	DW	Φ
5 CHANGE	← R−	4 −R	R	R	4 −Y−	4 −Y	G	G	R	R	R	R	R	R	DW	DW.	DΜ	DW	. ↓
DU1405 0 : 0		1 -	 		4 5	4.5									14/17	W112	D.W.	DW	

PED CLEAR/COUNTDOWN | ← R-2 + 6 CHANGE DW PHASE 4 & 8 PED CLEAR/COUNTDOWN |-R-DW DW 4 & 8 CHANGE DARK DARK DARK FLASHING OPERATION

WIRING DIAGRAM



WIRING KEY

- A,B PROPOSED ELECTRICAL CABLE 7-CONDUCTOR (NO.14 AWG)
- C PROPOSED INTERCONNECT 12-PAIR COMMUNICATION CABLE (INSTALL CABLE FROM CABINET TO CABINET)
- D,E,F MICRO-LOOP PROBE LEAD-IN CABLE
- ML NON-INVASIVE MICRO-LOOP PROBE
- (*) USE EXISTING ELECTRICAL CABLE



CHECKED BY _____ D. DICKERSON

F.A.P. NO. <u>AC-STPG-OOOA(832)</u>E

STATE OF MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION OFFICE OF TRAFFIC & SAFETY TRAFFIC ENGINEERING DESIGN DIVISION

MD 410 (EAST-WEST HWY) & TOLEDO TERRACE/ENTRANCE TO HOME DEPOT

GENERAL INFORMATION SHEET

HYATTSVILLE, MARYLAND

SCALE N	TS	ADVERTISED	DATE_	APR. 20, 2013	CONTRACT	NO.	XX4395185
DESIGNED B	Y N	M. KABENGELE		COUNT	y	ICE	GEORGE'S
DRAWN BY_	N	I. KABENGELE		LOGMIL	E	1604	1002.35

DRAWING TSP -02 OF 02 SHEET NO. 2 OF 2 TS NO. 278 E

PLOTTED: Tuesday, April 02, 2013 AT 12:40 PM FILE: J:\DATA\K887\Design Files\MD410&Toledo Terrace Gl.dgn