


MD 650 IS ASSUMED TO RUN
IN A NORTH-SOUTH DIRECTION


GENERAL NOTES

1. ALL TRAFFIC SIGNAL FOUNDATIONS SHALL BE INSTALLED AT FINAL SIDEWALK OR CURB GRADE FOR CLOSED SECTIONS. HIGHEST ROADWAY PROFILE GRADE FOR OPEN SECTIONS. TO MEET CLEARANCE AS SPECIFIED IN MD 816.03, MD 818.01, MD 818.02, MD 818.04. THE CONTRACTOR SHALL VERIFY ULTIMATE GRADES PRIOR TO THE INSTALLATION OF ALL SIGNAL EQUIPMENT.
2. ALL UNDERGROUND AND OVERHEAD UTILITIES SHOWN ON THESE PLANS ARE SCHEMATIC ONLY AND MAY NOT BE COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR NOTIFYING MISS UTILITY PRIOR TO THE CONSTRUCTION SO THAT ALL UTILITIES MAY BE LOCATED IN THE FIELD. IF THE CONTRACTOR PERCEIVES THAT A CONFLICT BETWEEN UTILITIES AND THE TRAFFIC SIGNAL WILL OCCUR, THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER IMMEDIATELY SO THAT THE CONFLICT MAY BE RESOLVED.
3. THE CONTRACTOR SHALL NOT CUT MAST ARM AS INDICATED ON PLANS UNTIL MAST ARM POLE LOCATION IS FINALIZED.
4. INSTALL CONDUIT PRIOR TO THE INSTALLATION OF PAVEMENT MARKINGS. REFER TO SIGNING AND PAVEMENT MARKING PLANS FOR ADDITIONAL DETAILS.
5. VERIFY PROPOSED GEOMETRICS PRIOR TO INSTALLING SIGNAL EQUIPMENT.
6. ALL HANDHOLES SHALL BE INSTALLED AT FINAL GRADE.
7. THE SIGNAL CONTRACTOR SHALL DETERMINE IF ANY WORK BY OTHER CONTRACTORS CAN NOT BE COMPLETED UNTIL INSTALLATION OF SIGNAL EQUIPMENT IS COMPLETE. THE SIGNAL CONTRACTOR SHALL NOTIFY OTHER CONTRACTORS OF THIS WORK.



PROPOSED SIGNS



PROPOSED SIGNAL HEADS



NEMA PHASING



CONSTRUCTION DETAILS

1. INSTALL 16.5 FT. (15'-0" T) STEEL POLE WITH A TWIN 50 FT. (CUT TO 35 FT.)/70 FT. MAST ARMS, TRAFFIC SIGNAL HEADS AND SIGNS. (INSTALL 1-2 IN. AND 1-4 IN. SCHEDULE 80, 90 DEGREE POLYVINYL CHLORIDE ELECTRICAL CONDUIT BENDS IN POLE BASE).
2. INSTALL 16.5 FT. (15'-0" T) STEEL POLE WITH A 60 FT. MAST ARM, TRAFFIC SIGNAL HEADS AND SIGN. (INSTALL 1-2 IN. AND 1-4 IN. SCHEDULE 80, 90 DEGREE POLYVINYL CHLORIDE ELECTRICAL CONDUIT BENDS IN POLE BASE).
3. INSTALL 10 FT. BREAKAWAY PEDESTAL POLE WITH COUNTDOWN PEDESTRIAN SIGNAL HEAD, AUDIBLE/ TACTILE PEDESTRIAN PUSHBUTTON INSTALLED WITH VIBRATING ARROW POINTING LEFT AND R10-4(1) SIGN. (SIGN TO READ "PUSH BUTTON TO CROSS NEW HAMPSHIRE AVE."). (INSTALL 2-2 IN. SCHEDULE 80, 90 DEGREE POLYVINYL CHLORIDE ELECTRICAL CONDUIT BENDS IN PEDESTAL BASE).
4. INSTALL NEMA SIZE "6" BASE MOUNTED CABINET AND CONTROLLER WITH CONCRETE PAD AND ELECTRICAL UTILITY SERVICE EQUIPMENT (120/240 V. 60 AMPS). (INSTALL 2-2 IN. AND 2-4 IN. SCHEDULE 80, 90 DEGREE POLYVINYL CHLORIDE ELECTRICAL CONDUIT BENDS IN CABINET BASE).
5. INSTALL HANDHOLE.
6. INSTALL 2 IN. SCHEDULE 80, POLYVINYL CHLORIDE ELECTRICAL CONDUIT (TRENCHED).
7. INSTALL 2 IN. SCHEDULE 80, POLYVINYL CHLORIDE ELECTRICAL CONDUIT (TRENCHED) FOR PROPOSED UNDERGROUND ELECTRICAL.
8. INSTALL 4 IN. SCHEDULE 80, POLYVINYL CHLORIDE ELECTRICAL CONDUIT (TRENCHED).
9. INSTALL 4 IN. SCHEDULE 80, POLYVINYL CHLORIDE ELECTRICAL CONDUIT (SLOTTED).
10. CUT, CLEAN, GALVANIZE AND CAP TRAFFIC SIGNAL STRUCTURE.
11. INSTALL 12 IN. WHITE HEAT APPLIED PERMANENT PREFORMED THERMOPLASTIC PAVEMENT MARKING (CROSSWALK).
12. INSTALL 24 IN. WHITE HEAT APPLIED PERMANENT PREFORMED THERMOPLASTIC PAVEMENT MARKING (STOP LINE).
13. INSTALL BASE MOUNTED METERED SERVICE PEDESTAL WITH 1-2 IN. AND 1-3 IN. SCHEDULE 80, 90 DEGREE CONDUIT BEND IN PEDESTAL BASE.
14. INSTALL 4 IN. SCHEDULE 80, POLYVINYL CHLORIDE ELECTRICAL CONDUIT (TRENCHED) FOR PROPOSED UNDERGROUND ELECTRICAL SERVICE. CAP AND MARK CONDUIT 2 FT. ABOVE GRADE AT UTILITY POLE FOR USE BY OTHERS.

LEGEND OF UNDERGROUND AND OVERHEAD UTILITIES

AERIAL CABLE	— A —
ELECTRICAL	— E —
TELEPHONE	— T —
GAS	— G —
SEWER	— SS —
STORM DRAIN	— SD —
WATER	— W —
CABLE TV	— TV —

WR&A
Whitman, Requardt
and Associates, LLP
801 South Caroline Street
Baltimore, Maryland 21231
(410) 235-3450

REVISIONS	APPROVALS
	TEAM LEADER - TRAFFIC ENGINEERING DESIGN DIVISION
	<i>Michal R. 5/10/06</i> ASST. TRAFFIC ENGINEERING DESIGN DIVISION
	<i>Wanda R. 5/10/06</i> CHIEF, TRAFFIC ENGINEERING DESIGN DIVISION
	<i>2/12/06</i> DIRECTOR, TRAFFIC & SAFETY

MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic & Safety
TRAFFIC ENGINEERING DESIGN DIVISION
TRAFFIC SIGNALIZATION PLAN
MD 650 AND LEBANON STREET

DRAWN BY: S. BLOSS	F.A.P. NO.	TS NO.	
CHECKED BY: N. LEARY	S.H.A. NO.	4473	
SCALE: 1" = 20'	COUNTY: PRINCE GEORGES	T.I.M.S. NO.	
DATE: 5/12/2006	LOG MILE: 16065002.03	H605	

SHEET NO.

54 OF 85

pk:\3145755\1\sp07m650.dgn