PROJECT DESCRIPTION

This project involves the installation of interconnect between MD 4 at Ward Road and MD 4 at Town Center Blvd./Dunkirk District Park.

PROJECT CONTACTS DISTRICT 5

MR. LARRY ELLIOTT
ASST. DIST. ENGR. TRAFFIC
410-841-1003

MR. CHARLES GEORGE
ASST. DIST. ENGR. MAINTENANCE
410-841-1002

MR. JOHN MAYS UTILITIES ENGR. 410-841-1005

MR. ERNIE HODSHON
ASST. DIST. ENGR. CONSTRUCTION
410-841-1004

CONTACTS FOR THE OFFICE OF TRAFFIC

MR. RICHARD DAFF CHIEF TRAFFIC OPERATIONS 410-787-7630

MR. ED RODENHIZER
TEAMLEADER SIGNAL OPERATION
410-787-7650

MR. EUGENE BAILEY
TEAMLEADER SIGN OPERATIONS
410-787-7676

MR. DAVE SCHWARTZ SUPPLY OFFICER SIGNAL WAREHOUSE 410-787-7666 A. EQUIPMENT TO BE FURNISHED BY STATE HIGHWAY ADMINISTRATION

ITEM NO. QUANTITY DESCRIPTION

9086 1 EA CABINET W/ TELEMETRY (SYSTEM CAB), SIZE 6

9087 1 EA CONTROLLER ASC II W/ TELEMETRY

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY CONTRACTOR

ITEM NO. QUANTITY DESCRIPTION 1001 2 EA MAINTENANCE OF TRAFFIC 8020 1 EA INSTALL CONTROLLER AND CABINET - BASE MOUNT 8027 1900 LF FURNISH AND INSTALL 3 INCH SCHEDULE 80 RIGID PVC CONDUIT - TRENCHED 8029 100 LF FURNISH AND INSTALL 3 INCH SCHEDULE 80 RIGID PVC CONDUIT - BORED 8033 10 EA FURNISH AND INSTALL ELECTRICAL HANDHOLE FURNISH AND INSTALL 12 PAIR COMMUNICATION CABLE, JELLYFILLED (UNDERGROUND) 3000 LF 1 EA DELIVERY OF REMOVED CONTROLLER AND CABINET

F.A.P. NO. <u>AC STPG 000S (686)E</u>

S.H.A. NO. XX1005585

COUNTY: <u>Calvert</u>

4074-X2

SHEET NO.

DRAWN BY: J. Henkel

Not to scale

4/01/2001

C. EQUIPMENT TO BE RETURNED TO STATE HIGHWAY ADMINISTRATION

0001 1 EA BASE MOUNTED SIZE 6 CABINET AND CONTROLLER

