


- INSTALL 2" SCHEDULE 80. RIGID PVC ELECTRICAL CONDUIT. TRENCHED.
- REMOVE EXISTING SIGNAL POLE, MAST ARM, SIGNAL HEADS, SIGNS, METER, DISCONNECT AND ALL OTHER EQUIPMENT ASSOCIATED WITH THIS MAST ARM. THE EXISTING POWER SERVICE WILL BE REMOVED BY OTHERS.
- REMOVE EXISTING OVERHEAD SIGNAL CABLE.
- F INSTALL GROUND ROD

- 1. SEE SIGNING AND MARKING PLAN FOR ALL OTHER SIGNS AND PAVEMENT MARKINGS. 2. ALL DETECTORS SHALL BE INSTALLED AFTER THE PAVEMENT GRINDING IS COMPLETE
- AND BEFORE THE FINAL SURFACE COURSE OF ASPHALT IS PLACED. 3. THE CONTRACTOR SHALL TEST PIT FOR EXISTING UTILITIES PRIOR TO INSTALLING
- ANY CONDUIT, FOUNDATIONS OR HANDHOLES.
- 4. ALL CONDUIT AND HANDHOLES UNDER PROPOSED SIDEWALK AND/OR DRIVEWAY APRONS SHALL BE TRENCHED AND IN PLACE PRIOR TO CONSTRUCTING THE PROPOSED SIDEWALK AND/OR DRIVEWAY APRONS.

GP-1 OF GP-5



MARYLAND DOT - STATE HIGHWAY ADMINISTRATION
Office of Traffic & Safety Office of Traffic & Safety TRAFFIC ENGINEERING DESIGN DIVISION SIGNAL PLAN

US 40 ALT AND MD 66 US 40 ALTERNATE: BOONSBORO

DRAWN BY: DMG CHECKED BY: GSJ S.H.A. NO. WA9605184 T.I.M.S. NO. COUNTY: JANUARY 2000 LOG MILE:

SHEET NO.