



***MD 7 (Philadelphia Road) from US 40 (Pulaski Highway)
to MD 588 (Golden Ring Road) in Baltimore County
Community Safety and Enhancement Program Project***

Fact Sheet – September 2007

Project: “Rosedale Streetscape” project to improve highway safety, traffic operations, pedestrian access and aesthetics along 2.55 miles of MD 7 (Philadelphia Road) in Baltimore County.

Limits: US 40 (Pulaski Highway) to MD 588 (Golden Ring Road)

Construction Cost: \$10.7 million

Features: Pavement grinding, patching, and resurfacing; replacement of sidewalks where needed; construction of ADA-compatible sidewalks and ramps; construction of new curbs, gutters, and drainage system improvements; corridor landscaping and installation of community signs and installation of gas utility line improvements.

The proposed improvements will include the following:

- Repair and overlay existing pavement.
- Repair/replace existing sidewalks.
- Extend sidewalk where needed.
- Re-stripe/install crosswalks where necessary.
- Modify the roadway to meet ADA standards.
- Accommodate bicycle compatibility with share use shoulder.
- Improve drainage and storm drain systems.
- Install/replace curb and gutter system.
- Install turn lanes where necessary.
- Relocate utilities as required.
- Upgrade Street lights at Kenwood Avenue.
- Improve landscaping and streetscape amenities.

Contractor: M. Luis Construction Co., Inc.

Schedule: Project Start: Summer 2007
Estimated Completion: Fall 2009

***MD 7 (Philadelphia Road) from US 40 (Pulaski Highway)
to Golden Ring Road in Baltimore County
Community Safety and Enhancement Program Project***

Page Two

**Construction
Staging:**

The contractor will work in three segments along the Philadelphia Road corridor, starting at US 40 and proceeding along the eastbound side of Philadelphia Road towards Chesaco Avenue. The next segment will be between Chesaco Avenue and Rustic Avenue, and the third section will be between Rustic Avenue to Golden Ring Road. The first phase of work will include the gas utility line upgrade/relocation, followed by curb and gutter and sidewalk construction.

After the eastbound side reconstruction is complete, the contractor will start the westbound side at US 40 and proceed east towards Golden Ring Road. The final surface paving along the entire project limit will be done once the corridor reconstruction is complete.

Project Status:

Gas line relocation work is underway on the first segment between US 40 and Chesaco Avenue. Overhead BGE pole relocations are near completion and Utility work will continue through Winter 2008

Work Schedule

and Lane Closures: During construction work, daytime lane closures along Philadelphia Road may occur anytime between 9 a.m. and 3 p.m. Monday through Friday.

Nighttime lane closures may occur anytime between 7 p.m. and 5 a.m. Sunday through Thursday.

SHA Contact Information

If you have any questions about the Rosedale Streetscape construction project, please contact:

Mr. David Bond
SHA Project Engineer, Rosedale Streetscape
Phone: 410-686-7780
E-mail: dbond@sha.state.md.us

(Vacant)
SHA Area Engineer for Baltimore County
Phone: 410-321-2823
Toll Free: 1-800-962-3077
E-mail: shadistrict4@sha.state.md.us

SHA Project Field Office
6506 Ridge Road
Baltimore, MD 21237

Please feel free to call or e-mail your questions or concerns about the project. We will be pleased to assist you.

