


NOTES

1. LONGITUDINAL UNDERDRAIN SHALL BE PLACED ACCORDING TO THE PLANS OR DIRECTED BY THE ENGINEER.
2. THE UNDERDRAIN TRENCH SHALL NOT BE CONSTRUCTED BEFORE PLACEMENT OF THE BASE (SUBBASE) COURSE.
3. LONGITUDINAL UNDERDRAIN TRENCH SHALL BE WRAPPED IN CLASS SD TYPE II GEOTEXTILE.
4. AGGREGATE SHALL CONFORM TO No. 57 AGGREGATE, 901.01 OF THE STANDARD SPECIFICATION FOR CONSTRUCTION AND MATERIALS.
5. AGGREGATE SHALL BE TAMPED WITH A LIGHT VIBRATORY TAMPER PRIOR TO OVERLAPPING THE GEOTEXTILE FABRIC.
6. CONTRACT UNIT PRICE BID PER LINEAR FOOT FOR 6" PERFORATED CIRCULAR PIPE LONGITUDINAL UNDERDRAIN SHALL CONSTITUTE FULL COMPENSATION FOR ALL MATERIALS, LABOR, EQUIPMENT AND INCIDENTALS NECESSARY TO DO THE WORK.
7. IF ANY EXISTING LONGITUDINAL UNDERDRAIN IS ENCOUNTERED DURING WIDENING EXCAVATION, THE UNDERDRAIN PIPE SHOULD BE REMOVED UNLESS OTHERWISE DIRECTED BY THE ENGINEER. ANY VOID CREATED BY THE REMOVAL OF THE UNDERDRAIN PIPE SHOULD BE BACKFILLED BY MATERIAL SUITABLE FOR EMBANKMENT CONSTRUCTION. IF NO LONGITUDINAL UNDERDRAIN IS FOUND, BUT EXISTING UNDERDRAIN OUTLETS MAY BE IMPACTED BY NEW WIDENING, OUTLETS SHALL BE CONNECTED TO THE NEW UNDERDRAINS OR OTHER DRAINAGE FACILITIES.
8. OUTLET THE UNDERDRAINS INTO OTHER DRAINAGE STRUCTURES WHENEVER POSSIBLE AT INTERVALS NOT TO EXCEED 250'. REFER TO STD. NOS. 387.11, 387.11-01, 387.21 AND 387.21-01.



GEOTEXTILE FABRIC
DETAIL

SPECIFICATION 306	CATEGORY CODE ITEMS
APPROVED	<i>[Signature]</i> DIRECTOR - OFFICE OF HIGHWAY DEVELOPMENT
	APPROVAL • SHA REVISIONS
	APPROVAL • FEDERAL HIGHWAY ADMINISTRATION
	APPROVAL 6-30-16
	APPROVAL 6-28-16
	REVISIONS

Maryland Department of Transportation
STATE HIGHWAY ADMINISTRATION
 STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES
LONGITUDINAL UNDERDRAIN LOCATED AT CURB & GUTTER EDGE FOR RIGID PAVEMENT

STANDARD NO. MD 387.21-01