


OPTION - 1 SEE NOTE 1



NOTES

- I. THIS WORK IS TO BE DONE AT THE CONTRACTOR'S OPTION. THIS I' WIDTH (MAXIMUM) EXCAVATION MAY BE USED FOR CURB AND GUTTER FORM PLACEMENT. THE ADDITIONAL EXCAVATION WIDTH IS TO BE FILLED WITH PCC MIX NO. 3 OR MIX 9 CONCRETE TO THE BOTTOM OF THE FINAL ASPHALT MIX COURSE. PAYMENT SHALL BE INCIDENTAL TO THE LINEAR FOOT ITEM FOR CURB AND GUTTER. JOINTS SHALL MATCH THOSE OF THE CURB AND GUTTER. NO DOWEL BARS ARE NEEDED.
- 2. ALL COSTS FOR ITEMS, MATERIALS, TOOLS, AND LABOR FOR EXCAVATION, PCC MIX, GAB, AND FULL DEPTH SAW CUT EXCEPT FOR ASPHALT MIX SURFACE SHALL BE INCIDENTAL AND INCLUDED IN THE PRICE OF THE LINEAR FOOT ITEM FOR CURB AND GUTTER.
- 3. REFER TO STANDARD NOS. MD 620.02 AND 620.02-01 FOR COMBINATION CURB AND GUTTER DIMENSIONS.

SPECIFICATION CAT	EGORY CODE ITEMS	MARYLAND DEPARTMENT OF TRANSPORTATION
APPROVED Lightmalelle		STATE HIGHWAY ADMINISTRATION
		STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES
APPROVAL SHA REVISIONS	APPROVAL FEDERAL HIGHWAY ADMINISTRATION	NEW COMBINATION CURB AND GUTTER
APPROVAL 2-25-16	APPROVAL 2-23-16	PLACEMENT ALONG EXISTING PAVEMENT
REVISED 10-27-22	REVISED 8-26-22	
REVISED	REVISED	STANDARD NO. MD 580.03
REVISED	REVISED	STANDARD NO. MD 300.03