4"TOPSOIL, SEED, AND MULCH
OR SODDING WHERE DIRECTED
BY ENGINEER

16" —— THREE (3) OR MORE CABLE DUCTS

12" —— TWO (2) CABLE DUCTS

8" —— ONE (1) CABLE DUCT

3" WIDE RED MARKING TAPE
BURIED 6" BELOW SURFACE
PRINTED WITH
"CAUTION ELECTRIC LINE BURIED BELOW"

6"

2'-0" MIN COVER
UPPER MOST LAYER

SELECT BACKFILL
MATERIAL OR APPROVED
MATERIAL EXCAVATED
FROM TRENCH

2'-0" MINIMUM

BARE COPPER
GROUND WIRE

3"

13" BACKFILL OF SAND OR
NO. 10 AGGREGATE

2"

4" CLEARANCE

2"

PREASSEMBLED CABLE DUCT

SECTION VIEW