


MINIMUM NUMBER OF SPANS = 2
 MINIMUM NUMBER OF POSTS = 3
 MAXIMUM SPAN: 12'-6"
 LENGTH OF BARRICADE NOTED ON PLANS: CENTER TO CENTER OF END POSTS
 ALL SPANS TO BE EQUAL LENGTH.
 NO. OF POSTS TO BE NOTED ON PLANS.
 ALL POSTS W6x9, 6'-0" LONG
 (SEE STD. MD 605.10)

NOTES

1. TRAFFIC BARRIER W BEAM BARRICADE SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER LINEAR FOOT. THE CONTRACT PRICE BID SHALL INCLUDE THE FURNISHING AND INSTALLATION OF ALL POSTS, W BEAM, POST AND SPLICE BOLTS WITH NUTS, END SECTIONS, GALVANIZING, THE COST OF ALL EXCAVATION, BACKFILLING AND TAMPING INCIDENTAL TO SETTING THE POSTS, OR THE COST OF DRIVING THE POSTS, THE COST OF THE REMOVAL OF EXISTING PAVEMENT WHERE NECESSARY, AS WELL AS THE COST OF ALL LABOR, APPROVED TOOLS AND EQUIPMENT INCIDENTAL TO FURNISHING AND INSTALLING THE BARRICADE AT LOCATIONS NOTED ON THE PLANS OR WHERE DIRECTED BY THE ENGINEER. FOR MATERIAL, SEE LATEST S.H.A. SPECIFICATIONS FOR TRAFFIC BARRIER W BEAM.

SPECIFICATION 605	CATEGORY CODE ITEMS
APPROVED	<i>[Signature]</i> DIRECTOR - OFFICE OF HIGHWAY DEVELOPMENT
APPROVAL SHA REVISIONS	APPROVAL FEDERAL HIGHWAY ADMINISTRATION
APPROVAL 3-21-61	APPROVAL 7-7-70
REVISED 8-16-12	REVISED 8-13-12
REVISED 12-21-17	REVISED 12-20-17
REVISED	REVISED

 MARYLAND DEPARTMENT OF TRANSPORTATION
 STATE HIGHWAY ADMINISTRATION
 STANDARDS FOR HIGHWAYS AND INCIDENTAL STRUCTURES
TRAFFIC BARRIER W BEAM BARRICADE
STANDARD NO. MD 605.27