## PROJECT DESCRIPTION

GENERAL

THIS PORTION OF THE PROJECT INVOLVES THE REMOVAL OF THE EXISTING CONTROL SIGNAL AT THE EXISTING INTERSECTION OF MD 450 (ANNAPOLIS ROAD) AND MD 704 (MARTIN LUTHER KING JR. HWY.) IN PRINCE GEORGES COUNTY. MD 450 IS ASSUMED TO RUN IN AN EAST-WEST DIRECTION.

SPECIAL NOTE

THIS SIGNAL IS NOT TO BE REMOVED UNTIL THE TEMPORARY CONNECTION SIGNAL FOR THE NEW MD 450 AND MD 704 INTERSECTION IS OPERATIONAL IN PHASE III STAGE I AND TRAFFIC IS SHIFTED.

THE EXISTING INTERCONNECT BETWEEN THE MD450 INTERSECTIONS WITH MD 704 AND MD 953 DOES NOT HAVE TO BE MAINTAINED.

72 HOURS PRIOR TO ANY WORK ON THE TRAFFIC SIGNALS, THE CONTRACTOR SHALL NOTIFY THE DISTRICT 3 TRAFFIC SECTION REPRESENTATIVE, MR. RICHARD BUETTNER (301-513-7316) AND THE SIGNAL OPERATIONS SUPERVISOR, MR. EDWARD RODENHIZER (410-787-7652).

## EQUIPMENT LIST "C"

C. EXISTING EQUIPMENT TO BE REMOVED BY THE CONTRACTOR AND DELIVERED TO THE STATE HIGHWAY ADMINISTRATION, 7491 CONNELLEY DRIVE, HANOVER, MARYLAND 21076. THE CONTRACTOR SHALL NOTIFY THE SHA AT (410) 787-7652 AT LEAST THREE DAYS IN ADVANCE OF DELIVERY.

I EA.

POLE MOUNTED CABINET/CONTROLLER

SEE TITLE SHEET

B. EQUIPMENT TO BE FURNISHED AND/OR INSTALLED BY THE CONTRACTOR

DESCRIPTION

CATEGORY

SECTION QUANTITY CODE NO.

800000

REMOVAL OF EXISTING TRAFFIC SIGNAL EQUIPMENT

EXISTING SIGNAL PHASE III STAGE 1

DWG. NO. TS - 10

MARYLAND DOT - STATE HIGHWAY ADMINISTRATION

Office of Traffic & Safety TRAFFIC ENGINEERING DESIGN DIVISION

MD 450 AND MD 704 (EXISTING LOCATION)

LOG MILE NO. 16045007.55 DATE 2/6/91

D. A. NIES D. DODA 7/25/91 CHECK BY: E. MILESKY 7/26/91 5.H.A. NO. P-98I-45I-385 PRINCE GEORGES

SHEET NO .: SHEET NO. TS-3167A-XI-GI

THE WILSON T. BALLARD CO. CONSULTING ENGINEERS OWINGS MILLS, MARYLAND

AUGUST 1996 - WTB MODIFY EXISTING SIGNAL SHA NO. PG9005171

a visions

APPROVALS

ASSI, DISTRICT ENGINEER, TRAFFIC

CHIEF, TRAFFIC ENGINEERING DESIGN DIVISIÓN

RECTOR, OFFICE OF TRAFFIC & SAFET)

ASST. DIVISION CHIEF. TEDD